# **Darden Installation Guide Book**

















# Introduction

Darden Restaurants is the world's largest company-owned and operated full-service restaurant company. Darden owns and operates more than 1,700 restaurants including Red Lobster, Olive Garden, LongHorn Steakhouse, The Capital Grille, Bahama Breeze and Seasons 52. ADT is the exclusive provider of Fire and Security in all new restaurants. We leverage our unique position to be the national vender Darden expects. Meeting the Darden Restaurant needs requires us to work as a team to meet our customer's expectations.

Our commitment to Darden is to provide Consistent, Quality, and On-Time Installations. There is no priority order for these goals. All are expected to be met on all sites.

The goal of the NASC is to provide a cooperative approach between the NASC team and Local managers. Together we will meet the customer's expectation and needs.

Darden has specific install dates and on site requirements for ADT. Darden's construction volume and professional construction management team enables a predicable schedule and accuracy in estimating completion times. Review the project schedule and communicate any challenges in meeting the schedule to the NASC team.

# Five areas are unique to the Darden Project

# **Cooler/Freezer Holdups**

Darden specifies a protected Freezer hold up inside any cooler or freezer door with a latch. The protection is detailed in the work book on Page 9. Confirm the field modified box is ordered by the Branch for the job. This is a Life Safety device! Proper installation and location is vital to protect the Hold Up for continued operation

## **Duct Smoke Detectors**

Darden specifies Trane HVAC units with duct detectors mounted in ducts below the unit. Review the installation diagram prior to starting wire pulls.

# **Energy Management Point of Connection**

Darden requires two connections to the CPI energy management panel.

## **Exterior Siren and Strobe**

The Strobe and Siren have separate connections; review the installation diagram prior to starting wire pulls.

# **Wire Routing**

When routing and securing wires or cables, all wire must be fully supported by the building structure including between trusses. Run wire in approved hangers, routed parallel to building lines, at right angles to building lines unless required by local authority having jurisdiction. Use Tie wraps for bundling and placing wire only (ADT Best Practices)



# **Project Schedule**

Darden Job Management will require a phased approach to installation. Review each phase to stay on track with meeting the Darden Completion Date.

# **Phase - 1 System Design and Customer Contract**

All systems are designed by the ADT Systems Engineering group in Birmingham AL. The branch Install Manager must sign off on any plans requiring more than 80 hours. Final contracts are created by the NAM using the local input and Darden requirements. Local management is encouraged to review ALL Fire Alarm Estimates prior to contract signature.

# Phase - 2 Booking and job distribution

Jobs are booked in Compass approximately 90 days before the turn over date. Detailed site specific plans are attached as a PDF file to every Compass estimate

#### **Phase - 3 Permitting**

Each jurisdiction has specific requirements regarding permitting Security and Fire Alarm submittal and approval. Each office is required to initiate permit applications within seven days of job receipt. Notify the National Account Support Team when the permit is applied for, expected return date and when the permit is issued. If a PE stamp is required, us local resources or request stamped drawings from GDS our national provider.

# **Phase - 4 Equipment ordering**

Equipment must be ordered within four weeks of pre-wire date. This is necessary due to the customer's request to have all control panels recessed in the office wall.

#### Phase - 5 Panel Deliveries

Three weeks before the prewire date, deliver the Fire Alarm Panel, NAC Power Supply and Security Alarm Panel to the general contractor. The General Contractor will recess the panels into the framing as part of the building structure. Return the Panel Receipt to the job file for future reference.

## Phase - 6 Site visit

The ADT Install Manager or CB PM will visit the site prior to prewire to deliver the permit and sealed plans to the General Contractor and review device placement with the Electrical contractor. It is the Electrical Contractors responsibility to install conduit and back boxes for wall mounted Fire Alarm devices. The Burglar system will require conduit for the keypad, the freezer/cooler holdups and the manager's office holdup. ADT BA and FA prints are included in the GC Master plans. Confirm the site plans match our permit set, any discrepancies cause unnecessary work. We must confirm exact conduit placement and review the dedicated 110 volt circuits in time to request corrections. Review the site plan for outside Sprinkler valves not on our plan; notify the NASC of any additional points requiring a rider.

#### Phase - 7 Kick Off conference call

The Project Manager or Installation Coordinator will schedule a conference call prior to prewire. The Install Manager, local project manager and installer or subcontractor should attend. The work plan, Install Guide and site specific drawings must be available for review.



#### Phase - 8 Pre-wire

Darden's expects the site will be pre-wired with two techs over a two or three day period and complete all wire runs. All contacts must be installed into frames as part of the prewire to allow painting to match the frame. All low voltage wire is to be supported by building structures or ADT provided supports, stringing wire between trusses is not acceptable.

## Phase - 9 Trim-out

The local installation team will perform all trim-out work possible when on site. We are to continue trim out regardless of site deficiencies. Confirm the availability of all Points of Connection and notify the GC of any issues. If power and phones are not present at time of trim-out, the installation coordinator must be notified. It is typical for restaurants to get power and phone at the last minute and schedule final inspections within 24 hours

# **Phase - 10 Inspections**

All inspections are to be coordinated by the local office with the GC and must be performed on dates established by the GC and Darden Project Manager. ADT must be on site for all inspections, any delays caused by ADT will be billed to the branch as per Darden contract.

# Phase - 11 Customer training and turnover

Manager training on the Burglar and Fire alarms will take place after the Certificate of Occupancy is issued when Darden Management reports on site. Contact NASC coordinator for confirmation of date and time. Customer will sign the ADT acceptance form after training.

# **Phase - 12 Quality Assurance Inspections**

A National Account project manager or NAFSS, not associated with the installation department will be performing the Quality Assurance inspection and returning digital pictures and the Darden QA form to our project team. A copy of the Quality Assurance Survey is attached. Photos of typical and acceptable installation methods will be provided in the QA guide. There is no reason that any site should not get a 100% score on this Survey.





10040000000009) Page 2 of 2



# **DARDEN WORK PLAN**

There are site specific BA and FA drawings for this restaurant. If you do not have these drawings, see the Installation Manager, or local ADT NAFSS for this job.

Only the Darden Project Manager (GC's boss) is authorized to make on site changes to the Work Plan or the site specific drawings. Notify the NASC Installation Coordinator of any change requests. Changes authorized by the Darden Project Manager should be documented and signed on a F5157-00 change order prior to starting any work. Changes to the Security System must be authorized by the Director of Corporate Security, Don Slaughter. Changes to the Fire Alarm must be approved by the ADT System FA Designer and the AHJ. The installer should acknowledge all change requests and immediately communicate those requests to the NASC.

# **GENERAL INSTALLATION NOTES:**


#### **Control Panels**

Control Panels are mounted inside the Manager's Office. The Electrical Contractors will accept delivery of the panels during the initial conduit walk through. They will mount and recess the panels as much as possible. Confirm the mounting depth does not hamper the panel door opening.

#### Phone Lines and Power

Phone Wires and Power are provided by customer. Phone Jacks are wired and punched down to the D-Mark by ADT. Phone jacks should be marked with the numbers for panel connection. Darden provides the numbers to ADT in advance; the NASC forwards the numbers to the Installation Manager. Please contact the ADT NASC Account Coordinator with ANY questions or concerns about the phone jacks or numbers.

**Technicians:** check with your installation manager and confirm the proper phone numbers per Darden's requirements. Failure to do so will result in another trip to make this happen. **Carter Brothers subcontractor:** please check with the Carter Brothers project manager.





# Security System

# Keypad:

BA Keypad is surface mounted to a single gang box inside the restaurant. See the site specific plans for location. Ensure the STI cover is mounted squarely over the Keypad.

#### Contacts:

All dining room doors are protected with embedded ¾" door contacts, and stand alone SIMs. Locate SIMs in 4x4 boxes above the ceiling; wall boxes with blank plates are not acceptable. Mechanical rooms, external storage areas and kitchen doors may be contacted with surface mount door contacts and may require weather tight flex to reach the area or install the contact. The Manager's Office door is protected with a recessed SIM contact. The Roof Hatch requires an Overhead Door Contact. The safe is mounted on a custom poured concrete pad in the manager's office. Pre-wire to the wall beside the safe pad and mount an ADT high security Hood Contact on the safe door.

#### **Motion Detectors:**

Motions are not to be prewired to electrical boxes, route the prewire to location on the diagram and secure the wire to a support stud.

Motion 1 wall mounted just inside the second set of double doors at the entrance protecting the entry area and looking toward the bar.

Motion 2 wall mounted in the corner of the dining room, next to an emergency exit door. If there is a soffit, mount it below the soffit.

Motion 3 Wall mounted outside of the Manager's Office Door, looking at the office.

#### **ADT Stickers:**

Apply ADT Security Stickers to every exterior door. Consult the manager before installing stickers on the main entry doors. Include an ADT NASC sticker on the Security panel.

#### Programming Notes:

Codes are sub-programmable; The Master Code will be assigned ONLY to the General Manager, No exceptions. All manager codes should be programmed as "by-passable". Ensure download programming auto answer is programmed for a minimum of 12 rings. The initial call list can include the General contractor for the Fire Alarm inspection. Ensure the managers update the call list as part of the final training. Confirm Arm Code user 88 is programmed as duress with store number as code. For example, if the store number is 1842 the duress code will be 881842. Send one duress code in test signals.

#### Zone Assignment:

Darden does not specify a zone template. Assign the zones sequentially and provide a zone list during management training.

### Hold Up Office:

The Manager's Office gets an armored covered Hold Up Alarm (HUA) mounted under the desk, not on the wall. Route and secure the wire under the desk.



# Point of Connection to Lighting Control System:

Mount two Horn Strobe SIM modules above the Carolina Products Inc (CPI) Energy Management System to control the lighting system.

Program the SIM connected to ALI as Type 68 ABA, connect to relay as Comm./ NC Program the SIM connected to ALA as Type 20 OFC connect to relay as Comm./ NO

Confirm each output is operational by watching the MASTER PLC in the panel. LED 5 is lit when input ALI is correctly connected, it is out during alarm conditions. LED 4 is out when input ALA is correctly connected, it is on when the system is armed.

All CPI inputs are non-functional until programmed by the factory. Nomad group will test and program the system just after Fire Testing. Any deficiencies are reported to Darden and will require a return trip by ADT to correct the issues and redo testing with CPI factory programmer to enable the point.

Every installer is responsible to confirm the ADT/CPI interface is correctly operating as designed for energy optimization. All panel programs, wiring to the CPI panel and materials are ADT's responsibility; no other trades are needed to complete connections per plan.

ADT Security system must be completed immediately after the Fire system is inspected. A full function test of all points and signaling including checking the CPI on-board LED indicators is required.

One week before management turnover, the NASC will notify the branch to schedule demonstration and testing of the CPI connection with Darden's commissioning group Nomad. Nomad is on site one day only and expects to test the ADT/CPI connection in the afternoon. The Nomad engineer is familiar with the interface operation and will provide guidance if needed. After Nomad witness a complete cycle of system arm, alarm, disarm they will report a successful system test to CPI. CPI will program the master control to activate on ADT input.


If commissioning with Nomad is not completed as scheduled, we must complete testing before turn over and notify the NASC testing is complete. The NASC will confirm arm activity in MAS and notify CPI to review history and confirm the interface is operational and logging activity. CPI will confirm operation and turn on the ADT interface.

If any irregularities are noted in the log ADT will return to correct the connection. The tech must contact the ADT project manager for technical support. The PM will engage CPI for a live test to confirm connections.

CPI will email the Darden Design Group with successful tests.

See the schematic on the next page.








# Exterior Siren & Strobe:

Mount the exterior siren cabinet in the rear service area 10' above the finished grade level with the strobe on the face of the siren cabinet. Connect the tamper switch to a security panel zone. Connect the strobe to the Horn Strobe SIM module. The siren will time-out but the strobe will continue to flash until the panel is reset. Connect the siren to the panel Bell 1 output. Connect the Siren Cabinet Tamper switch to any zone in the Focus panel.







# Hold Up Freezer:

**IMPORTANT** The walk-in coolers and freezer get the Sentrol Low temperature HUA P/N 3045CTW-ADT inside the locking door.

Mount 18" (+/-) a.f.f., about 6" from the hinge side. Check with the GC to find out where the Stainless Steel shelves are going, confirm the HUA button is not hidden by the shelf. HUA buttons are installed only inside LOCKABLE areas. This is a Life Safety device! Proper installation and location is vital to its ability to operate properly.

The Electrical Contractor will provide conduit inside the freezer terminated in either a single gang box or an LB.

The HUA go inside a plastic 4"X4" "weatherproof" j-box with no cover and the top center cut out. The purpose is if anyone is tied up and on the floor, they can get their foot in the box and activate the HUA. The HUA MUST be protected from damage to avoid false alarms

The plastic "weatherproof" j-box HUA should be mounted so that you must <u>pull it down to activate</u>. Please file the edges of the j-box, smooth. The Stand Alone SIM, used for "zoning" these buttons CAN NOT be mounted in the coolers or freezer. Mount the SIM above the unit in a box.

Seal the inside and outside of the conduit to prevent warm air from outside the freezer condensing in the box





# Fire Alarm System

#### **FA INSTALLATION NOTES**

This FA panel is an addressable "stand alone" panel not connected to the BA system. All devices are connected with 18 gage 2 conductors FPLP turned cable.

#### Conduit

Darden provides conduit drops and boxes for the wall mounted and exterior Fire Devices. ADT provide ceiling mount boxes and supports. Review the device placement, box size and routing during the initial on site walk through with the EC and GC. Depending on local requirements, some sites may require conduit to exterior Horn Strobes, Post Indicator Valves or Gate Valves, confirm box placement and the possible need for underground conduit with the GC and EC.

#### Remote Annunciator

Surface mounted to a single gang box in the corner of the foyer, as noted on the site specific plan.

## Horn/Strobe Lights

Ceiling mount NAC devices are used in the dining area. ADT is to provide all ceiling mount boxes and support bars. Do not mount ceiling devices on decorative beams; adjust the location to place the NAC in the center of the ceiling panel. Strobes located in the freezer/cooler can be red. Seal the inside of the cooler/freezer conduits to prevent warm air from outside the freezer condensing into the back box. If the AHJ requires an external Horn Strobe, confirm the GC modifies the building finish to accommodate the external device.

#### Manual Pull Station

Surface mounted to a single gang box at each exit as directed on the site specific plan.

#### Smoke Detector

Typically, one is mounted in the manager's office above the FA Panel or as directed on the site specific plan. One may be need above the Annunciator per local code.

#### Sprinkler Point(s) of Connection

Monitor all necessary points on the Waterflow switches, Tamper switches, and Gate or PIV valves. Confirm the points found on site match the site specific plan, report any devices not listed in the plan to the Account Coordinator. It is the installer's responsibility to confirm the POC are ready prior to final inspection.


#### Remote Test Switches

Keyed Remote Test Switches are mounted inside the Manager's office. Wire using 18 gage four conductors as per the diagram. Label professionally with a label gun.




Duct Detectors Darden provides duct detectors mounted below the HVAC units. ADT is to provide power and connect to the Alarm and Supervisory contacts to Monitor them. Locate the Monitor modules beside the HVAC unit within site of the duct detector. Program the Fire Panel for either "Supervisory" or "Fire," signals on Duct Detector activation as per local AHJ requirements. All units will have a Control Relay program as local or global shutdown per local ordinance. Locate the control relay inside each unit adjacent to the Trane ESTOP POC, refer to the diagram.

### SYSTEM WIRING DIAGRAM FOR DUCT SMOKE DETECTORS



## **Ansul System**

Darden provides a Dry Contact Micro switch on the tank as the Ansul Point of Connection. Connect the monitor module to terminals screw terminal only. All other points are not listed for Fire Alarm connection and may cause unexpected results. If the Micro Switch is not available, notify the GC and the account coordinator to clear the point.



CRF-300

RTS 451 KEY

(Red LED)

Alarm

(2)

(4)

SLC LINE



To



# **Darden Panel Receipt**

Red I	Lobster/Olive	Garden/ Longhorr	n Capital Grill/ Bah	ama Breeze #	
Stree	et Address				
City			State	Zip	
frami pane with	ing, conduit a Is are to be m	the Alarm Panel bo and finish application and finish application ounted in the man masters. Review thents.	on in prior to our <i>F</i> nager's office per t	ADT prewire date. he approved plan	All s included
		Fire Alarm Panel 19"H x 16 5/8 W x 5 3/8D S 24 FS8 Power Supply 15"H x 14 1/2 W x 2 3/4 D			
	ADT Focus Cadet Security Panel 18 1/4 H x 14 1/4 W x 4 5/8 D				
Job S	Site Superinte	endent			
Print	Name		Cell Phone _		
Signa	ature				



# **Suggested Framing details**

